




**IPAC'22, Bangkok, Thailand, June 12-17, 2022**



# **High intensity ion beam accelerator facilities HIAF and CiADS status and demonstration of key technologies**

**Hongwei Zhao**

**On behalf of HIAF&CiADS team**

**Institute of Modern Physics (IMP),  
Chinese Academy of Sciences, Lanzhou, China**



# OUTLINE

- **Brief introduction and construction status of HIAF & CiADS**
- **Key technology R&D and demonstration**
  1. High-intensity highly-charged heavy ion beam production
  2. Fast ramping power supply with full energy storage
  3. Magnetic alloy core loaded RF system
  4. 17-20 MeV/CW 5-10 mA front-end demo-facility of proton SC linac **for CiADS**
- **Summary and conclusion**

} **for HIAF**



# HIAF&CiADS brief introduction

- **HIAF:** High Intensity heavy ion Accelerator Facility
- **CiADS:** China Initiative Accelerator Driven System
- Being built by IMP in Huizhou of Guangdong Prov.
- Two of 16 large-scale scientific infrastructure facilities approved by China Government during the 12<sup>th</sup> 5-year-plan 2016-2020

- **HIAF:** Nuclear physics research
- **Total budget:** 2.8 B CNY ¥ (424 M USD \$)
- **Schedule:** 2018-2025
- Construction started officially Dec. 2018

- **CiADS:** Nuclear waste transmutation
- **Total budget:** 4.0 B CNY ¥ (606 M USD \$)
- **Schedule:** 2021-2027
- Construction started officially July. 2021






# HIAF layout and parameters


## External target station

Nuclear Matter  
Hyper-nuclear  
High-E irradiation



## HIAF key parameters

	SECR	iLinac	BRing	HFRS	SRing
Energy (MeV/u)	0.014 (U <sup>35+</sup> )	17 (U <sup>35+</sup> )	835 (U <sup>35+</sup> )	800 (U <sup>92+</sup> )	800 (U <sup>92+</sup> )
Intensity	50 pμA (U <sup>35+</sup> )	28 pμA (U <sup>35+</sup> )	2×10 <sup>11</sup> ppp (U <sup>35+</sup> )	-----	10 <sup>10</sup> ppp (U <sup>92+</sup> )
Operation mode	DC	CW or pulse	fast ramping 12T/s 3Hz	Momentum -resolution 1100	DC, deceleration
Emittance or Acceptance π·mm·mrad dp/p		5 / 5	200/100 0.5%	±30/±15 ±2%	40/40 1.5%



**iLinac:**  
Superconducting linac injector



# HIAF technical challenge

- **High-intensity highly-charged heavy ion beam production and acceleration**
- **Two-phase painting injection to increase BRing injection efficiency and overcome space charge limit**
- **Fast ramping rate (12T/s) of BRing magnets to mitigate ionization beam loss and dynamic vacuum effect**

## **Key technology R&D and Prototyping**

- **28 GHz SECRAI-II and 45 GHz FEER ECR ion sources**
- **Fast ramping power supply with full energy-storage technology for BRing dipole magnet**
- **Magnetic alloy core loaded RF system**

# Civil construction site

HIAF-SRing tunnel

HIAF-BRing tunnel

CiADS

HIAF

CiADS site

Equipment test building  
No.2

HIAF operation building  
No.2

1# Cryogenic center


Office building No.1

Office building No.2

Cooling water building

Electric-power  
transformer station

Equipment test building  
No.1





# HIAF civil construction status








# HIAF components fabrication

■ Most of the components are in mass production





BRing dipole magnets




Components of HFRS superconducting magnets



iLinac HWR015 cavities



Components of SRing electron cooler



BRing collimator





# HIAF planed milestones and time schedule

2019	2020	2021	2022	2023	2024	2025
<b>Civil construction</b>						
		Electric power, cooling water, compressed air, network, cryogenic, supporting system, etc.				
ECR design & fabrication		SECR installation and commissioning				
	iLinac design and fabrication			iLinac installation and commissioning		
Prototypes of PS, RF cavity, chamber, magnets, etc.			fabrication	BRing installation & commissioning		
				HFRS & SRing installation & commissioning		
				Terminals installation		
Day One exp.						


- The first ion beam provided by **SECR** in the end of 2022;
- The first ion beam from **iLinac** in the end of 2024;
- The first ion beam injected, accelerated and extracted from **BRing** in May 2025



# CiADS layout and parameters

**CiADS could be the world first MW-level ADS facility**

- **T1: Fast reactor, LBE target**  
Demonstrate high power ADS and transmutation
- **T2: Target exp., liquid metal and granular target**
- **T3: material irradiation and full power dump**
- **T4: low power dump 50 kW**




## CiADS key parameters

Thermal Power (Reactor + Beam)	10 MW
Proton beam Energy (MeV)	500
Beam density (mA)	5
Operation modes	CW / Pulse
Target Max. power (MW)	$\leq 2.5$
Target material	LBE
Reactor $K_{eff}$	$\sim 0.75 / \sim 0.96$
Reactor thermal power	$\sim 7.5 / \sim 9.76$




# Physics design of CiADS proton linac



## Parameters of the SRF cavities

	HWR010	HWR019	HWR040	Ellip062	Ellip082
<b>Freq. (MHz)</b>	162.5	162.5	325	650	650
<b>Quantity</b>	9	24	60	30	28
<b>Dyna. load @ 2K</b>	2.9	4.4	5.7	23	25
<b>Ep @ op. (MV/m)</b>	26	28	28	29	29
<b>Ep @ cp. (MV/m)</b>	31	32	31	31	32



Beam envelope along the linac



# CiADS technical challenge

- **Minimize the beam loss and maintain a long-term high reliability and availability of the high power proton SC linac (500 MeV/5mA)**
- **High power spallation target (2.5 MW). Phase I: LBE target; Phase II: Granular flow target**
- **Coupling between the reactor, the target and the high power proton beam**

## Key technology R&D and Prototyping

- **17-20 MeV/CW 5-10 mA front-end demo-facility of CiADS linac for reliability demo.**
- **Target prototype R&D ( LBE target and granular flow target)**
- **Prototyping for fast subcritical reactor vessel, heat exchanger and LBE centrifugal Pump**




# CiADS civil construction status






# CiADS facility in prototyping and engineering design




650 MHz SSAMP @ 150 kW




HWR010


HWR015



HWR040




Ellip082



Ellip062


SRF cavities



Target Prototype



# CiADS planed milestones and time schedule






# OUTLINE

- HIAF & CIADS brief introduction and construction status
- **Key technology R&D and demonstration**
  1. **High-intensity highly-charged heavy ion beam production**
  2. Fast ramping power supply with full energy storage
  3. Magnetic alloy core loaded RF system
  4. 17-20 MeV/CW 5-10 mA front-end demo-facility of proton SC linac
- Summary and conclusion






# High-intensity highly-charged heavy ion beam production by SECRAL II



Ion Beam	SECRAL (eμA) (2015-2019)
$^{16}\text{O}^{6+}$	<b>6700</b>
$^{40}\text{Ar}^{12+}$	<b>1420</b>
$^{40}\text{Ar}^{16+}$	<b>620</b>
$^{40}\text{Ar}^{18+}$	<b>15</b>
$^{40}\text{Ca}^{11+}$	<b>710</b>
$^{78}\text{Kr}^{18+}$	<b>1030</b>
$^{78}\text{Kr}^{28+}$	<b>146</b>
$\text{Xe}^{26+}$	<b>1100</b>
$\text{Xe}^{30+}$	<b>365</b>
$\text{Xe}^{42+}$	<b>16</b>
$^{209}\text{Bi}^{31+}$	<b>680</b>
$^{209}\text{Bi}^{41+}$	<b>100</b>
$^{209}\text{Bi}^{50+}$	<b>10</b>
$^{238}\text{U}^{33+}$	<b>450</b>
$^{238}\text{U}^{35+}$	<b>315</b>




■ Demonstrated a good long-term stability

**Record beam intensities (red numbers) produced by IMP SECRAL I & II**




# The world first 4<sup>th</sup> generation ECR ion source FECR



## FECR key parameters

Microwave	45 GHz/20 kW
Magnet conductor	Nb <sub>3</sub> Sn
Axial fields (T)	6.5/1.0/3.5
Sextupole field (T)	3.8@r=75 mm
Maximum field (T)	11.8 T
Maximum stress (MPa)	150
Magnet bore (mm)	>Ø160
Stored energy (MJ)	1.6
Extraction (kV)	50
Typical beam	1.0 emA U <sup>35+</sup>



- Beams and intensities expected from FECR

- 3-5 times higher than the existing record beam intensities


$^{129}\text{Xe}^{30+}$	>1000 $\mu\text{A}$
$^{129}\text{Xe}^{45+}$	> 50 $\mu\text{A}$
$^{209}\text{Bi}^{31+}$	>1000 $\mu\text{A}$
$^{209}\text{Bi}^{55+}$	> 50 $\mu\text{A}$
$^{238}\text{U}^{35+}$	>1000 $\mu\text{A}$
$^{238}\text{U}^{41+}$	> 200 $\mu\text{A}$
$^{238}\text{U}^{56+}$	> 30 $\mu\text{A}$



# FECR Nb<sub>3</sub>Sn magnet




The magnet mechanical structure was designed by collaboration with ATAP magnet group at LBNL

## Bladder & Keys assembly







# 1/2 Prototype of FECR Nb<sub>3</sub>Sn magnet



## ■ Sextupole was energized only



## ■ Sextupole and one solenoid were energized




- Manufacturing and 8 times energizing tests of the 1/2 prototype Nb<sub>3</sub>Sn magnet took more than **5 years**
- The sextupole quenched at 70%-90%, sextupole+one solenoid reached 77% design current
- 2 of the 6 sextupole coils turned out to have performance degradation or minor damage
- Learned a lot of lessons and experiences, manufacturing, assembling, quench protection, flux jump, ....



# FECR full-scale $\text{Nb}_3\text{Sn}$ magnet status

**Almost ready for cooling down and energizing  
But need to verify the quench protection system carefully**




**The magnet was manufactured and assembled by collaboration with XSMT company in Xi-an**



# Fast ramping power supply with full energy storage for dipole magnets

- To reduce beam loss , 12 T/s ramping rate is required for the HIAF BRing dipole magnets.
- Challenge for the dipole power supply: High peak power, very fast ramping rate (38000 A/s), high tracking precision, very low current ripple and voltage fluctuation.

Excitation current/voltage	3900A/3600 V 3 Hz
load inductance	116 mH
Load Resistance	36.4 mΩ
Current changing rate	$\pm 38000$ A/s
Flat top/top/bottom error	$\leq \pm 0.2$ A $\leq 5.1 \times 10^{-5}$
tracking error	$\leq \pm 0.2$ A $\leq 5.1 \times 10^{-5}$




- A innovative power supply topology and technology proposed for HIAF BRing dipole magnets

Variable forward excitation; full energy storage technology; high-power-pulse technology with FPGA-based full-digital controllers.



# Prototype of fast ramping power supply with full energy storage

- A prototype power supply with full current and power has been developed. The key technologies and the innovative design with variable forward excitation and full energy storage technology at high-power pulse have been verified.




The prototype power supply was tested successfully with 4 real BRing dipole magnets connected in series  
**Achieved results: maximum current 4000 A/3600 V, ramping rate 38000 A/s  
repetition rate 3 Hz, tracking error  $\pm 9.62 \times 10^{-5}$**




# Magnetic alloy core loaded RF system for HIAF BRing

- RF system of HIAF BRing: high RF voltage 240 kV and short rise time  $\leq 10\mu\text{s}$  for beam compression



Voltage and phase waveform



- MA core production line was built through collaboration between IMP and a domestic company


- Key technology:** 14 $\mu\text{m}$  ribbon production, ribbon shearing, 1~2 $\mu\text{m}$  insulation silica coating, constant tension horizontal winding, atmosphere annealing and water proof coating



Ribbon shearing



1~2 $\mu\text{m}$  silica coating



Constant tension horizontal winding



Atmosphere annealing



Water proof coating





# Performance of the magnetic alloy core produced

## ■ Independent development of MA core


Over ten years development from small( $\phi 90$ ), medium ( $\phi 460$ ), to large size ( $\phi 780$ ) MA core.




95 × 65 × 25mm



460 × 230 × 25mm





750 × 345 × 35mm



780 × 360 × 35mm

## ■ Breakthrough in MA core manufacturing Q value: (0.65~0.3) @ (0.1~20MHz) $\mu'_p Q_f$ : 5.3GHz @ 0.3MHz





# Oil-cooling MA core loaded cavity and RF system manufactured




MA RF system




Two-TH558-tube amplifier cabinet

RF power test was carried out: Gap voltage/one cavity **50kV@0.3~2.1MHz**


The third harmonic suppression better than 25 dB




Cavity pick-up voltage



Voltage of ramping mode



Harmonic suppression




Harmonic at ramping mode




# 17-20 MeV/5-10 mA front-end demo facility for CiADS linac

- 2011-2017. SC linac 10-25 MeV/ CW 0.2-1.1 mA  
IMP collaborated with IHEP.
- 2018- 2021. Upgrade to 20 MeV/CW 10 mA  
Demonstrate 10 mA CW beam



ions	P, H <sub>2</sub> <sup>+</sup> , α
Frequency	162.5 MHz
Current	10 mA
E <sub>in</sub> RFQ	40 keV
E <sub>out</sub> RFQ	3.1 MeV
E <sub>out</sub> SC linac	20/30/40MeV
Cryo. Temp.	4.5 K


- Supported by “Strategic Priority Research Program” of the Chinese Academy of Sciences.





# High power CW SC proton linac reliability demonstration



- Operation from Jan. 20 to Mar. 10, 2021 **The world first demonstration**



Availability: 126.1 kW, op. time **108 hs**, availability **93.6%**

Beam current: 174.4 kW, **10.08 mA**, op. time 12 hs

High power: 20.18 MeV, 10.18 mA, beam power **205.5 kW**



CM2-1 coupler Vac

IS arc, R manually




# RAMI analysis for the continuous operation test

**Operation Period:** 9:42, Mar. 4, 2021 ~21:43, Mar. 8, 2021;


**Operation time:** 108 hrs (pre-set by the reviewers)

**Downtime:** 6.85 hrs, 93.6% availability

## Distribution of downtime and trips from subsystem



108 hours operation at 17.18MeV/7.5mA



12 hours operat. 17.27MeV/10mA

Trip sources	Downtime (s)		Trips		Avg time (s)
RF	6360	26%	18	41%	353
Cryogen.	0	0%	0	0%	0
Ion source	1103	4%	8	18%	138
Vacuum	7598	31%	3	7%	2533
Magnet	0	0%	0	0%	0
PS	1244	5%	2	5%	622
Diagn.	35	0%	1	2%	35
Control	8317	34%	12	27%	693

- Failures and trips caused by ion source, vacuum, PS and control can be solved.
- RF contributes the main parts of the trips



# Summary and Conclusion

## ■ HIAF and CiADS facilities being built in Huizhou by IMP.

- Most of HIAF components in mass production and civil construction completed 50%. The first beam commissioning of iLinac and BRing planed in 2024-2025.
- CiADS in key technology R&D and facility engineering design. The first beam commissioning of CiADS linac is planed in June 2025.

## ■ Key technology R&D and demonstration for HIAF&CiADS, achieved a good progress.

- A lot of record beam intensities for highly charged heavy ions were produced by SECRA II. 45 GHz FECR Nb<sub>3</sub>Sn magnet almost ready for cryogenic energizing after 7 years development.
- Fast ramping power supply with full energy storage successfully developed for HIAF BRing dipole magnet, reached 4000 A/3600 V, ramping rate 38000 A/s, 3Hz.
- Large size and high performance MA core was developed successfully. Oil-cooling MA core loaded cavity and RF system were manufactured and tested, reached designed performance.
- Reliability and availability at 17 MeV/CW 7.5 mA for 108 hours and 17 MeV/CW 10 mA for 12 hours continuously operation were demonstrated for the first time for a proton SC linac, as a low energy demo-facility for CiADS.



# Acknowledgement

**Thanks Jiangcheng Yang, Yuan He and Liangting Sun for preparing a few slides !**

**Thanks HIAF and CiADS teams for hard working and achieving good progress !**

**Thanks a lot all those experts and colleagues from the domestic and international Labs for your help, collaborations and fruitful discussions !**

**Thank you for your attention !**