


ELENA (Extra Low Energy Antiproton): from commissioning to operation



L. Ponce

On behalf of the operation and commissioning teams
with special thanks to D. Gamba, C. Carli and Y. Dutheil




Outlines

- Introduction
- Beam commissioning timeline
- Operation overview
- Beam performances of the first physics run



The CERN accelerator complex


Introduction: CERN Antiproton factory




- Antiprotons are produced by the 26 GeV proton beam from CERN PS impacting an irridium target
- $3.5 \cdot 10^7$ antiprotons at 3.5 GeV/c are captured in AD (Antiproton Decelerator)
- Antiproton deceleration to 100 MeV/c in AD
- 5 experiments connected to AD up to end of 2018
- ELENA project approved in 2011 to increase the capture efficiency of the traps operated by experiments
 - further deceleration from 5.3 MeV down to 100 keV kinetic energy

ELENA: Extra Low ENergy Antiproton

- Small 30.4 m circumference synchrotron connected after AD to decelerate antiprotons from 5.3 MeV to 100 keV
- Magnetic elements in the ring and electrostatic ones in the transfer lines:
 - 125 m of beam lines to deliver beam to 8 different users
- Local 100 keV H⁻ ion source:
 - Instrumental for commissioning of the transfer lines
- Electron cooling to preserve low transverse and longitudinal emittances during deceleration
- Available intensity distributed into 4 bunches sent to up to 4 experiments




Commissioning timeline:



Mid november:
First injection of H⁻

2018: Setting-up of
acceleration/deceleration
cycle



2020: beam commissioning
of transfer lines

H- operation

Installation
activities

Antiproton
operation

e-cooler
installation

2016

2017

2018

2019

2020


2021

CERN Long Shutdown 2: **no antiproton**
Installation of new transfer lines

June 2017:
first pbars injection


August 2017:
pbars circulating

22/05/2018: first
pbars at 100 keV





Decision to connect all
users to ELENA

20/07/2018: 1st Pbar beam
observed at entrance of Gbar



28th August 2021:
Start of first physics run






phosphor screen upstream of ALPHA catching trap

ELENA planning adjusted to general CERN planning


A closer look at 2018 beam commissioning

- Commissioning plan with alternance of H⁻ and pbars:
 - 3 pbar shift/week planned till end of July
 - Setting-up of accelerating/decelerating H⁻ cycle
- Progress with ELENA despite issues with beam(s) availability:
 - 65% machine availability for AD affecting physics as well as ELENA commissioning with antiprotons (pbars)
 - H⁻ operation compromised due to several breakdowns of the source High Voltage isolation transformer
- ELENA start-up end of April – equipped with electron cooler
 - 22/05: first beam observed at 100 keV after tune corrections throughout the cycle
 - 2/7: first signs of effect of electron cooling, first in longitudinal and transverse planes a couple of weeks later
 - 20/7: first antiprotons received by the first user of ELENA
- Reasonable deceleration efficiency (~45%), beam survival at 100 keV and transfer to GBAR obtained the last week of the run:
 - => **Decision confirmed to connect all users to ELENA**


Schottky signal



During LS2: Installation of new extraction lines



fast deflector plus static deflector to channel a single bunch towards a different line



Example of a horizontal profile taken just after extraction

Installation of new beam lines to transport and distribute bunches to every experimental area:

- 239 electrostatic elements, almost 500 power converters
- Fast deflector proved capable of deflecting single bunch with rise & fall time < 1us
- More than 40 beam profile monitors:
 - Partially interceptive micro-wire grids for measurement of the beam size and position
 - The comprehensive coverage of the lines was critical for commissioning

Complex timing system to distribute available bunches to up to four experiments in the same cycle



All bunches in the ring:




1 bunch in LNE50

2 bunches in LNE00

1 bunch not extracted

2020-2021: Extraction lines beam commissioning

- Characterization of beam profile monitors:
 - Found several wires in several monitors not working, but overall quality sufficient for commissioning
- Modelling and commissioning
 - Extensive modelling of the optical effects of the electrostatic devices during the design using tracking tools
 - Systematic optical characterisation of the beam delivered to every line was done during commissioning
 - No rematching as measured optics found close to design




Comparison at the end of the longest line of a tracking-based model from 2015 and a measurement taken in 2021 agree within 20% without corrections

Operation overview: pbars cycle

- Operational deceleration cycle is 13 s long:
 - Injection pbars from AD at 100 MeV/c
 - Deceleration to 35 MeV/c on RF h=1,
 - Electron cooling of debunched beam at 35 MeV/c
 - Rebunching and deceleration to 13.7 MeV/c on h=4
 - Electron cooling of debunched beam at 13.7 MeV/c
 - Re-bunching on h=4 with e-cooling on




Intensity measurement available only for bunched beam

Cycle optimized using mimic cycle with H⁻ ion beam, including the e-cooling setting-up in 2020-2021



Operation overview: operation mode



- ▶ ELENA cycle short compared to AD cycle (~2min)
 - H- cycles possible between antiproton cycle
- ▶ New mode of operation with respect to pre-LS2 time:
 - Four bunches per cycle sent to up to 4 users
- ▶ The extra low energy of the beam makes it very sensitive to stray magnetic fields:
 - stray field generated by the AEGIS experiment caused large distortions of the trajectory in ALPHA






1 G.m of transverse integrated magnetic field induces a deviation of around 2 mrad

Beam performance: delivered pbars

- ▶ ELENA deceleration efficiency and delivered bunch intensities well above design values (despite lower intensity from AD than 2018):
 - Uncertainty (of 10-15%) on calibration/signal treatment of instruments (measurement with optimistic calibration)
 - Profile monitors are semi-interceptive device (about 10 % beam loss per monitor)



Beam performance: extracted antiproton parameters



- Energy spread and bunch length within or better than design
 - Bunch length could be further reduced with bunch rotation at expense of energy spread
- Typical emittances of $2\mu\text{m}$ rms are about factor 2 larger than design (factor ~2 better than 2018 estimate!)
 - Working on adjusting the length of bunched beam cooling before extraction in ELENA to get smaller emittance
 - We observed clear emittance-intensity dependence to be investigated

=> Overall reached close to nominal beam characteristics

Beam parameters summary

Parameter	design	Achieved in 2021
Q_x/Q_y	~2.3/~1.3	2.37/1.85
Cycle duration [s]	20	13
Injected intensity [pbars]	3e7	>3.2e7
Deceleration efficiency [%]	60	85
Extracted bunches	4	4
Bunch population [pbars]	4.5e6	> 6e6
$\Delta p/p_0$	5e-4	4.5e-4
Bunch length (rms) [ns]	75	<75
Transverse emittances x/y [μm]	1.2/0.75	~2/~2

Summary

- ▶ **ELENA** and its new **transfer lines** have been **successfully commissioned during summer 2021**
 - **From autumn 2021 new era for antimatter physics with** 100 keV antiproton beams delivered to all experiments
- ▶ **Beam characteristics very close to design values:**
 - Easy to get **shorter bunches** than design, but transverse **emittances still a factor 2 bigger than nominal**
 - **Higher intensities than design** in ELENA
- ▶ **Extremely useful first run** in 2021 for both **operation and users** :
 - Experience gained on operation with **4 bunches available** on demand **at any time** to any experiments
 - Experience during the commissioning strongly validated the early choice of using electrostatic devices only for the transfer lines
 - Pretty **good orbit stability** of beam delivery in transfer lines:
 - Still **strong impact of experiment magnetic fields** when switching **on/off**
 - **H⁻ source operation very useful** for **ELENA** and **transfer line** set-up, but also for **experiment** setup/optimization (higher repetition rate)

Thank you

